

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-195-21455-00-00

LEASE NAME Ridgeway

WELL NUMBER 1

SPOT LOCATION App NW NW SW

SEC. 28 TWP. 12 RGE. 21 ~~E~~ & ~~R~~ (W)

COUNTY Trego

Date Well Completed 3-6-1984

Plugging Commenced 3-6-1984

Plugging Completed 3-6-1984

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Staab Oil Company

ADDRESS HC39 Box 114, Hays, Ks. 67601

PHONE # (913) 675-5013 OPERATORS LICENSE NO. 6037

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. 67601

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	249	8 5/8"	249	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

- 1st. Plug set at 1660' with 25 sacks common cement 50-50 Poz 6%Gel 3%Cal cl.
- 2nd. Plug set at 900' with 100 sacks common cement 50-50 Poz 6%Gel 3%Cal cl. with 1 sack seal 10 flake
- 3rd. Plug set at 280' with 40 sacks common cement 50-50 Poz 6%Gel 3%Cal cl
- 4th Plug set at 40' with solid bridge and 10 sacks common cement 50-50 Poz 3%Cal cl. 6%Gel 10 sacks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Oilwell Cementing License No. _____
 Address Hays, Ks. 67601

STATE OF Kansas COUNTY OF Graham, ss.

Jerry M. Helberg

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, help me God.

RECEIVED
 STATE CORPORATION COMMISSION
 03-15-1984
 MAR 15 1984

(Signature) Jerry M. Helberg
 (Address) Box 32 Morland, Ks. 67650

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1984

Wichita, Kansas

Coleen A. Waggoner
 Coleen A. Waggoner Notary Public

