

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-02216-0000  
API NUMBER 7-15-55

LEASE NAME Schneider

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2  
3300  
~~660~~ Ft. from S Section Line  
2970 ANB KCC  
~~330~~ Ft. from E Section Line

LEASE OPERATOR Coastal Oil & Gas Corporation  
ADDRESS 211 N. Robinson, Suite 1700, Okla. City, OK 73102

SEC. 32 TWP. 10 RGE. 20 (X) or (W)  
COUNTY Rooks

PHONE# (405) 239-7031 OPERATORS LICENSE NO. 6593

Date Well Completed 7-15-55

Character of Well oil

Plugging Commenced 3-25-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-28-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #4, Hays, Kansas

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Lansing Depth to Top 3564 Bottom 3600 T.D. 3775'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	oil	3564	3600	8-5/8"	323	---
				5-1/2"	3775	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf @ 156' w/3 spf & 852' w/3 spf. Pump 25 sxs Thrifty-mix dn. 5-1/2" csg., followed by 4 sxs CSH. 150 sxs Thrifty-mix. Max. Press. 900#. Pump 35 sxs Thrifty-mix. 1 sx. CSH dn. annulus. Max. Press 700#. Cutoff csg. 3' BGL. weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. n/a

Address Hays, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

C. Brad Crouch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. So help me God.

(Signature) C. Brad Crouch

(Address) 211 N. Robinson, Suite 1700, OKC, OK 73102

APR 11 1988  
SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 88

CONSERVATION DIVISION  
Wichita, Kansas  
Jackie Raapdal  
Notary Public

My Commission Expires: February 11, 1992