

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

#4 15-163-02217-0000  
 API NUMBER 5-15-64

LEASE NAME Schneider

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #3  
1650  
1980 Ft. from N Section Line  
1650  
1980 Ft. from W Section Line

LEASE OPERATOR Coastal Oil & Gas Corporation  
 ADDRESS 211 N. Robinson, Suite 1700, Okla. City, OK 73102

SEC. 32 TWP. 10S RGE. 20 (X) or (W)  
 COUNTY Rooks

PHONE# (405) 239-7031 OPERATORS LICENSE NO. 6593

Date Well Completed 5-15-64

Character of Well oil

Plugging Commenced 3-25-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-28-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #4, Hays, Kansas

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3691 Bottom 3700 T.D. 3775'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil	3691	3700	8-5/8"	235	---
				5-1/2"	3691	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf 5-1/2" csg. @ 1555', 3 spf & 850', 3 spf. Pump 25 sxs Thrifty-mix, 4 sxs CSH, 175 sxs Thrifty-mix dn 5-1/2" csg. Max. Press 1000#. Pump, 50 sxs Thrifty-mix, 1 sx CSH dn annulus. Max. Press. 800#. Cutoff 3' BGL & weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. n/a

Address Hays, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

C. Brad Crouch (Employee of Operator) or (Operator) of above-described well, being first sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained in the log of the above-described well as filed that the same are true and correct to help me God.

(Signature) C. Brad Crouch

(Address) 211 N. Robinson, Suite 1700, OKC, OK

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 88

Jackie Ragsdale  
 Notary Public

My Commission Expires: February 11, 1992