

5/15/84

15-163-21535-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Rooks SEC. 32 TWP. 10 RGE. 20W E/W
 Location as in quarters or footage from lines:
NE SE SE

Lease Owner Petroleum, Inc.
 Lease Name McKenna "D" Well No. "D" #4
 Office Address Box 1447, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced December 12, 1983
 Plugging completed December 30, 1983
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom _____ T.D. 3722'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	245'	None
				5-1/2"	3725'	2567.17'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped 5 sacks cement on bottom, sanded to 3670' and dumped 5 sacks
cement. Shot casing at 3300', 3000', 2750' and 2500'. Pulled 63 joints
5-1/2" casing. Squeezed well with 2 sacks hulls, 50 sacks cement,
1 sack hulls, 10 sacks gel, 70 sacks cement, 1 sack hulls, 15 sacks gel,
1 sack hulls, and 70 sacks 50/50 Pozmix cement with 6% added gel and
3% calcium chloride. Maximum pressure 300 psi and shut in 100 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold, Box 698, Great Bend, Ks. 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1984

IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-87


Iona M. Leatherman
 Notary Public.

My Commission expires:

STATE CORPORATION COMMISSION

JAN 16 1984

CONSERVATION DIVISION
 Wichita, Kansas



15-163-21535-0000

DRILLERS LOG

OPERATOR: Petroleum, Inc.
 Box 1447
 Great Bend, Kansas 67530

WELL NAME: #4 McKenna 'D'
 NE SE SE
 Sec.32-10S-20W
 Rooks County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 1/1/82

COMPLETED: 1/8/82

Surf. Casing: 8-5/8" set at 245' with 175 sx cement

Prod. Casing: 5-1/2" set at 3725' with 100 sx cement

0' to 250'	Surf. Hole
250' to 2410'	Shale
2410' to 2878'	Lime & Shale
2878' to 3082'	Shale & Lime
3082' to 3449'	Lime & Shale
3449' to 3726'	Lime & Arbuckle
RTD 3726'	

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the drillers log for the #4 McKenna 'D' for Petroleum, Inc.

James C. Remsberg
 James C. Remsberg, President

Sworn and subscribed this 30th day of November, 1983

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1985

