


15-163-01004-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 36 Twp. 10 Rge. 20 (EX (W))
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Veeder Supply and Development Co. et al
Lease Name Keller Well No. 2
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 24 1957
Application for plugging filed January 24 1957
Application for plugging approved January 24 1957
Plugging commenced January 24 1957
Plugging completed January 24 1957
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3732 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200' w/150 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 190' with 1/2 sack hulls, 15 sacks cement; mud to 40';
set plug with 1/2 sack hulls and 10 sacks cement; cemented to bottom
of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or (owner of operation) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1957


My commission expires July 11, 1960

RECEIVED
STATE CORPORATION COMMISSION
Eldon Petty
Notary Public.

PLUGGING
FILE NO. 36 T 10 R 20W
BOOK PAGE 137 LINE 30

FEB 1 1957
2-1-57
CONSERVATION DIVISION
Wichita, Kansas

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Aurora Gasoline Company
Producers Pipe & Supply Co.

Drilled for Veeder Supply & Development Co. et al Farm _____ Keller _____ No. 2 Depth 3732'

Contractor Veeder Supply & Development Co. Pipe 200' 8 5/8" csg. w/150 sacks 2%CC

Location NE/4 NW/4 SW/4 _____ Sec. 36 Twp. 10S Range 20W

Commenced 1-14-1957 Completed 1-24-1957 County Rooks State Kansas

Shale sand	0	120	120	Elevation: R. B. 2082	
Blue shale	120	200	80	Tops:	
Shale	200	510	310	Topeka	3117 -1035
Shale and sand streaks	510	985	475	Heebner	3332 -1250
Sand and shale	985	1165	180	Toronto Lime	3352
Shale, red bed	1165	1505	340	Lansing-KC	3370 -1288
Anhydrite	1505	1540	35	Base Kansas City	3580
Shale shells	1540	1995	45	Basal Penn. Cong	3627 -1601
Shale, lime streaks	1995	2070	75	Simpson Shale	3664
Shale lime	2070	2255	185	Arbuckle	3687
Lime shale	2255	3210	955		
Shale lime	3210	3231	21		
Lime	3231	3408	177		
Cherty lime, lime	3408	3443	35		
Lime	3443	3655	212		
Lime shale	3655	3680	25		
Shale lime	3680	3703	23		
Arb. lime	3703	3732	29		
T. D.					

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Keller #2 well located in Section 36-10S-20W. Rooks County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By: C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 28th day of January, 1957.

[Signature]
Notary Public

My commission expires July 11, 1960.

PLUMBING
FILE 36-10-20W
BOOK 187-30

RECEIVED
COMMISSION
FEB 1 1957
COUNTY CLERK