

15-163-20895-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 36 Twp. 10 Rge. 20WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW NW


Lease Owner Calvin Noah
Lease Name Trabach Well No. 1
Office Address 329 No. Birch, Valley Center, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed March 16 19 79
Application for plugging filed (verbally) March 16 19 79
Application for plugging approved (verbally) March 16 19 79
Plugging commenced March 16 19 79
Plugging completed March 16 19 79

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3720'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3720'

Set 1st plug at 600' with 70 sacks
2nd plug at 215' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 2:15 a.m., 3-16-79.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 19 79

Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

15-163-20895-0000

CONTRACTOR'S WELL LOG

OPERATOR: Calvin Noah
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Trabach #1
 LOCATION: SE NW NW, Section 36-10-20W
 Rooks County, Kansas
 SPUD DATE: March 06, 1979
 COMPLETION DATE: March 16, 1979

0	228	Surface clay and shale
228	705	Shale
705	1317	Shale and sand
1317	1546	Shale
1546	1585	Anhydrite
1585	3087	Shale
3087	3191	Shale and lime
3191	3690	Lime
3690	3720	Shale
	3720	Rotary Total Depth

Spud hole at 6:30 p.m., March 6, 1979. Drilled 228' of 12 1/4" hole. Ran 5 joints of 8-5/8" - 28# surface casing. Set at 225.26' with 165 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 6:00 a.m., March 7, 1979.

T.D. 3720'. Set 1st plug at 600' with 70 sacks, 2nd plug at 215' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 2:15 a.m., March 16, 1979.

SAMPLE TOPS:

Anhydrite 1541'
 B/Anhydrite 1584'

RECEIVED
 STATE CONSERVATION COMMISSION
 MAR 21 1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Trabach #1, SE NW NW, Sec. 36-10-20W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 20th day of March, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.