

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6039
Name: L.D. Drilling, Inc.
Address 1: 7 SW 26th Avenue
Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Contact Person: Mike Kasselmann
Phone: (620) 793-3051
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-24462-00-00
Spot Description: N/2 SE NW
_____ Sec. 30 Twp. 19 S. R. 12 East West
3,630 Feet from North / South Line of Section
3,300 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Harris Well #: 8
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Bruce Rodie (KCC District Agent's Name)
Plugging Commenced: 11-30-09
Plugging Completed: 12-01-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	302	None
			4-1/2"	3459	324'

RECEIVED
DEC 07 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3200' and 4 sacks cement. 4-1/2" casing parted @324', laid down 4-1/2", ran 2-3/8" tubing to 900'. pumped 300 sacks cement and circulated to surface. Couldn't pull tubing, backed tubing off, laid down 7 jts. Tied onto surface, pumped 20 sacks cement with 150# hulls, pressured up to 300#. Plugging complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: _____
City: Chase State: Kansas Zip: 67524 + 0 4 6 7
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso