

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33725  
Name: Foundation Energy Management, LLC.  
Address 1: 14800 Landmark Blvd. Suite 220  
Address 2: \_\_\_\_\_  
City: Dallas State: TX Zip: 75254 + 1434  
Contact Person: David Koss  
Phone: ( 918 ) 585-1650  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 159-21154-0002  
Spot Description: NW SE SE  
NW SE SE Sec. 19 Twp. 20 S. R. 9  East  West  
707 Feet from  North /  South Line of Section  
996 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Rice  
Lease Name: Edward Malone Well #: 1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Plugging Commenced: 11-25-09  
Plugging Completed: 11-27-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	211'	None
			4-1/2"	3359'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated casing @1250', 850' and 250'. Dumped 2 sacks cement on top of bridge plug @2165'. Ran 2-3/8" tubing to 1250'. pumped 35 sacks cement, pulled tubing up to 850', couldn't tag cement. Ran tubing back to 1250', pumped 35 sacks cement, pulled tubing up to 850', couldn't tag cement. Ran tubing back to 1250'. pumped 35 sacks cement. Laid tubing down, cement @160'. Ran tubing to 160' and circulated 20 sacks to surface. 60/40 pos, 4% gel. Plugging Complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.  
Address 1: P.O. Box 467 Address 2: \_\_\_\_\_  
City: Chase State: Kansas Zip: 67524 + 0467  
Phone: ( 620 ) 938-2943  
Name of Party Responsible for Plugging Fees: Foundation Energy Management, LLC.  
State of Kansas County, Rice, ss.  
Mike Kelso  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 07 2009

KCC WICHITA