

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Popp Operating, Inc.

Address: PO Box 187, Hoisington, KS 67544-0187

Phone: (620) 786-5514 Operator License #: 32325

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Case Morris (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Arb Depth to Top: 3303' Bottom: 3306' T.D. _____
L-KC Depth to Top: 3104' Bottom: 3160' T.D. _____
Platt Depth to Top: 2938' Bottom: 42' T.D. _____

API Number: 15 - 167-23373-00-00

Lease Name: Michaelis "A"

Well Number: #1

Spot Location (QQQQ): NW - NW - SE -
2,160' Feet from ☐ North / ☒ South Section Line

2,310' Feet from ☒ East / ☐ West Section Line

Sec. 36 Twp. 15 S. R. 14 ☐ East ☒ West

County: Russell

Date Well Completed: _____

Plugging Commenced: 11/03/09

Plugging Completed: 11/05/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	865'	
				5 1/2"	3,399'	2,260'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand was at 2,880'; Bailed 5 sacks cement with bailer. Ripped casing at 2,450' and 2,260. Pulled casing up to 1,500'; Pumped 150 sacks of 300# hulls. Pulled to 900'; Pumped 40 sacks of 100# hulls. Pulled to 500'; Pumped 50 sacks of 100# hulls. Pulled to 200'; Circulated with 45 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Popp Operating, Inc.

State of Kansas County, Barton, ss.


Rickey Popp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rickey Popp

(Address) PO Box 187 Hoisington, Ks.

SUBSCRIBED and SWORN TO before me, this 30th day of November, 2009

My Commission Expires: 5/20/2011



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

DEC 02 2009

KCC WICHITA

D6

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3881

Date	11-4-09	Sec.	36	Twp.	15	Range	14	County	Russell	State	Ks	On Location		Finish	5:00 P.M.	
Lease	Michaelis		Well No.		A#1		Location									Russell Back Co. 15th
Contractor	Quality Well Service							Owner								1 E 1/2 N W into
Type Job	PTA							To Quality Oilwell Cementing, Inc.								
Hole Size	7 7/8							T.D.								
Csg.	5 1/2							Depth								
Tbg. Size								Depth								
Tool								Depth								
Cement Left in Csg.								Shoe Joint								
Meas Line								Displace								
EQUIPMENT																
Pumptrk	5	No.	Cementer	JOE												
Bulktrk	11	No.	Driver	Brian												
Bulktrk	PV	No.	Driver	TODD												
JOB SERVICES & REMARKS																
Remarks:																
1st Plug 1500'																
150x 60/40 Poz 4% GEL w/ 300# hulls																
Disp w/ H2O																
2nd Plug 900'																
40x 60/40 Poz 4% GEL w/ 100 hulls																
Disp w/ H2O																
3rd Plug 500'																
50x 60/40 Poz 4% GEL w/ 100# hulls																
Disp w/ H2O																
Pull up to 200'																
Circ out to surface																
4.5x 60/40 Poz 4% GEL																
Amount Ordered																
275x 60/40 Poz 4% GEL																
Common																
165																
Poz. Mix																
110																
Gel.																
10																
Calcium																
Hulls																
500#																
Salt																
Flowseal																
Handling																
285#																
Mileage																
08 REC & Poz M. 1.5																
FLOAT EQUIPMENT																
Guide Shoe																
Centralizer																
Baskets																
AFU Inserts																
Pumptrk Charge																
PTA																
Mileage																
1.6																
Tax																
Discount																
Total Charge																

Thanks
TODD JOE BEAN
Signature

PLEASE
CALL
AGAIN

RECEIVED
DEC 02 2009
KCC WICHITA