

7 **Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Popp Operating, Inc.
 Address: PO Box 187, Hoisington, KS 67544-0187
 Phone: (620) 786-5514 Operator License #: 32325
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Case Morris (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Arb Depth to Top: 3291' Bottom: 3297' T.D. _____
L-KC Depth to Top: 3202' Bottom: 3262' T.D. _____
Platt Depth to Top: 2830 Bottom: 2836' T.D. _____

API Number: 15-009-24723-0000
 Lease Name: Panning
 Well Number: #1
 Spot Location (QQQQ): C - N/2 - NE - SE
2,310' Feet from North / South Section Line
825 Feet from East / West Section Line
 Sec. 11 Twp. 20 S. R. 11 East West
 County: Barton
 Date Well Completed: _____
 Plugging Commenced: 11/05/09
 Plugging Completed: 11/09/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	505'	
				5 1/2"	3,375'	2,240'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulled 50 joints tubing. Pulled slips; Had 18" stretch. Sand was at 2,780'. Bailed 5 sacks cement with bailer. Ripped casing at 2,410' and 2,240'. Pulled casing up to 1,400'; Pumped 150 sacks of 300# hulls. Pulled to 550'; Pumped 60 sacks of 100# hulls. Pulled to 200'; Circulated with 55 sacks to surface. Pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Popp Operating, Inc.

State of Kansas County, Barton, ss.

Rickey Popp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rickey Popp

(Address) P.O. Box 187 Hoisington KS

SUBSCRIBED and SWORN TO before me this 30th day of November, 2009

Jane M. Steinert My Commission Expires: 5/20/2011
Notary Public



RECEIVED
DEC 02 2009
KCC WICHITA

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3883

Date	11-9-09	Sec.	11	Twp.	20	Range	11	County	Barton	State	Ks	On Location		Finish	5:00 P.	
Lease	Pannings			Well No.	#1			Location	Barton Rig Co line							
Contractor	Quality Well Service							Owner	I W M S W into							
Type Job	PTA							To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.								
Hole Size	7 7/8			T.D.												
Csg.	5 1/2			Depth	Charge To POPP OPERATING											
Tbg. Size				Depth	Street											
Tool-				Depth	City State											
Cement Left in Csg.				Shoe Joint	The above was done to satisfaction and supervision of owner agent or contractor.											
Meas Line				Displace	CEMENT											
EQUIPMENT								Amount Ordered	265 5x 60/40 Poz 40% Gel							
Pumptrk	5	No.		Cement Helper	JOE			Common	159							
Bulktrk	3	No.		Driver	Rocky			Poz. Mix	106							
Bulktrk	PJ	No.		Driver	Tono			Gel.	9							
JOB SERVICES & REMARKS								Calcium								
Remarks:								Hulls	400							
1st Plug 1400'								Salt								
150x 60/40 Poz 40% Gel w/ 300# hulls								Flowseal								
DISP w/ H2O																
2nd Plug 550'								Handling	274							
60x 60/40 Poz 40% Gel w/ 100# hulls								Mileage	109 Poz 5x Per mile							
DISP w/ H2O																
3rd 200'								FLOAT EQUIPMENT								
CIRC CUR TO PZT								Guide Shoe								
55x 60/40 Poz 40% Gel								Centralizer								
								Baskets								
								AFU Inserts								
								Pumptrk Charge	PTA							
								Mileage	10							
Thanks								Tax								
Tono JOE Rocky								Discount								
PLEASE CALL PANNING								Total Charge								
X Signature <i>[Signature]</i>																

RECEIVED
DEC 02 2009
KCC WICHITA

