



Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION 1033445  
 OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
 K.A.R. 82-3-117

Form CP-4  
 March 2009  
 Type or Print on this Form  
 Form must be Signed  
 All blanks must be Filled

OPERATOR: License #: 5030  
 Name: Vess Oil Corporation  
 Address 1: 1700 WATERFRONT PKWY BLDG 500  
 Address 2: \_\_\_\_\_  
 City: WICHITA State: KS Zip: 67206 + 6619  
 Contact Person: W.R. Horgan  
 Phone: (316) 682-1537  
 Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Viola Depth to Top: 2522 Bottom: 2530 T.D. 2600  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. ~~15~~-15-015-19671-00-00  
 Spot Description: NE SE SE  
SE NE SE SW Sec. 33 Twp. 25 S. R. 5  East  West  
750 Feet from  North /  South Line of Section  
2,350 Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Butler  
 Lease Name: PIERPOINT A Well #: 97  
 Date Well Completed: 11/25/1960  
 The plugging proposal was approved on: 11/30/2009 (Date)  
 by: Duane Krueger (KCC District Agent's Name)  
 Plugging Commenced: 12/02/2009  
 Plugging Completed: 12/02/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Viola	saltwater, slight oil	2522-2530	8.625	207	0
Simpson (sqz)	saltwater	2552-2570	5.5	2599	0
			4.5	2488	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing to 2500'. Load hole. Spot 57 sx Class A, 3% cc @ 2500'. Pull tubing. Wireline tag cement @ 1930'; Perf holes at 300'. Run tubing to 500'. Mix and pump 30 sx 60/40 pozmix, 4% gel, 3% cc, pull out. Wireline tag @ 515'. Run tbg to 310'. Pump 50 sx. Circ. Pull out, tie on 4-1/2", pump add'l 100 sx 60/40 pozmix, 4% gel. Holding pressure - finished 3:00 p.m.

Plugging Contractor License #: 32991 Name: Simmons Well Service, Inc.  
 Address 1: 6730 SE SATCHELL CRK RD Address 2: \_\_\_\_\_  
 City: LEON State: KS Zip: 67074 + 7918  
 Phone: (316) 745-8772  
 Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
 State of Kansas County, Sedgwick, ss.  
 \_\_\_\_\_  
 (Print Name)  Employee of Operator or  Operator on approved design

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 DEC 11 2009  
 CONSERVATION DIVISION  
 WICHITA, KS

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten Signature]*