

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33629 **RECEIVED**  
Name: Great Plains Energy, Inc.  
Address 1: PO Box 292 **SEP 23 2009**  
Address 2: 429 N. Linden  
City: Wahoo State: NE Zip: 68089 **KOOWICHITA**  
Contact Person: Dan Blankenau  
Phone: ( 402 ) 277-5336  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
None Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. ~~5~~ - 15-109-20819-00-00  
Spot Description: \_\_\_\_\_  
E/2 .NE. NW. SW Sec. 10 Twp. 13 S. R. 32  East  West  
2,310 Feet from  North /  South Line of Section  
1,260 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Logan  
Lease Name: Wieland Well #: 1  
Date Well Completed: 9/23/08  
The plugging proposal was approved on: 3/19/09 (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 7:45am 3/21/09  
Plugging Completed: 12:00pm 3/21/09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface, Conductor & Production) |        |               |            |
|---------------------------|---------|---|--------|---------------|------------|
| Formation                 | Content | Casing  | Size   | Setting Depth | Pulled Out |
|                           |         | Surface   | 8 5/8" | 251'          | None       |
|                           |         | Production                                      | 5 1/2" | 4668'         | 1465'      |
|                           |         |   |        |               |            |
|                           |         |   |        |               |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4300' above top perforations. Dumped two sacks cement on plug. Worked pipe to figure stretch. Made cut @ 2495'-could not pull. Made cut @ 2200'-could not pull. State plugging orders required cement @ 2200'. Ran tubing to spot first plug. Perforated four holes @ 2200'. Ran tubing and spotted 50 sacks cement. Tripped out of hole with tubing. Made cut @ 1475'-5 1/2" casing came free. Spotted 60 sacks. Plug @ 1450'. Pulled casing to 450'. Spotted 80 sack plug. Pulled to 260'. Spotted 20 sack plug. Pulled casing out of hole. Filled with cement. Recovered 1465' of casing.

Plugging Contractor License #: ~~34066~~ 33755 <sup>KCCPKT per CP2/B</sup> Name: Trinity Oilfield Services <sup>Quality Plus oilfield Services LLC</sup>

Address 1: PO Box 307 Address 2: \_\_\_\_\_

City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_

Phone: ( 620 ) 564-3005

Name of Party Responsible for Plugging Fees: Great Plains Energy, Inc.

State of Nebraska County, Saunders, ss.

Daniel F. Blankenau  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]

*[Handwritten mark]*