

15-065-01677-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1966
WICHITA, KANSAS

Operator's Full Name Union Texas Petroleum,
Complete Address: Drawer "D", Great Bend, Kansas.
Lease Name P. A. Miller Well No. 8
Location SE-SE-SW Sec. 3 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3854
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Santa Fe Pipe and Supply, Incorporated.
Address: Box # 562, Great Bend, Kansas. License No. 574
Operation Completed: Hour 12:00M Day 9 Month 5 Year 1966

The Above well was plugged as follows:

202'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3852'--5 1/2" Production casing. Well plugged back to 3752'. Perforations
from 3540' to 3546'. Well squeezed in the Dakota Sands with 350 Sx. cement.
No attempt made to salvage 5 1/2" casing.

Attempted to squeeze well with gel but gel broke out of surface pipe below
braden head. Pumped plug down 5 1/2" casing and followed with measuring line
to determine hole in 5 1/2". Plug stopped @ 1113'. Circulated cement to
bottom of cellar by pumping in 5 1/2" and returning thru hole in surface pipe
below Braden head. Closed well in. Checked well after cement had time to
set and found fluid level @ 75' and cement plug @ 2028'. Ran 2" tubing to
600' and set 8 Sx. "Quick-Set" cement thru 2". Waited 1 hour, checked
plug with tubing and circulated cement to top of 5" casing using 65 Sx.
cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 5/11/66
INV. NO. 3198-W