

15-065-01004-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 2 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Rocket-Schusterman Oil Account,

Complete Address 1209 Mid-Continent Building, Tulsa, Oklahoma.

Lease Name Miller Well No. 9

Location SE-SW-SW Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3905'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Allied Cementing Company, Incorporated,

Address Box #207, Russell, Kansas. License No.     

Operation Completed: Hour 8:00 PM Day 27 Month 12 Year 1973

The above well was plugged as follows:

198'--8 5/8" Surface casing, cement circulated.  
3904'--5 1/2" Production casing cemented on bottom. Top perforations from 3804' to 3811'.  
Well plugged back to 3832'. 5 1/8" has been squeezed in the Cedar Hills.  
Squeezed 5 1/2" casing initially with 3 sacks hulls and 25 sacks cement then 30 sacks gel  
and finally 60 Sx. cement. Maximum pump-in pressure-600#. Final shut-in pressure-  
450#. Pressured annulus to 500# with no leakage.

I hereby certify that the above well was plugged as herein stated.

DATE 1/4/74  
INV. NO. 8359-W

Signed: A. L. Dohak  
Well Plugging Supervisor