



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company,

Complete Address P. O. Box #287, Great Bend, Kansas.

Lease Name Tribble Well No. 4

Location 330' FWL & 330' FNL of NE/4 Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3881'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address P. O. Box #105, Chase, Kansas. License No. 624

Operation Completed: Hour 2:30 PM Day 26 Month 11 Year 1974

The above well was plugged as follows:

291'--8 5/8" Surface casing, cement circulated with 300 Sx.
3872'--5 1/2" Production casing cemented on bottom with 200 Sx. (Open hole Completion).
After shooting 5 1/2" casing upward from 2600' with 16 shots found that 5 1/2" had been
squeezed w/cement into surface casing.

Sanded well back to 3860' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(221') and squeezed well initially with 1 sack hulls and 12 sacks gel following with
150 Cu. Ft. cement then 8 sacks gel and followed with 30 Cu. Ft. cement then 5 sacks
gel and finally 10 Cu. Ft. cement. Maximum pump-in pressure-600#. Final shut-in
pressure-600#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/4/74
INV. NO. 395-w