

15-065-02581-0001

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rocket-Schusterman Oil Account,
Complete Address 1209 Mid-Continent Building, Tulsa, Oklahoma.
Lease Name Miller Well No. 7
Location SW-NW-SW Sec. 3 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 4300'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Allied Cementing Company, Incorporated,
Address Box #207, Russell, Kansas. License No.
Operation Completed: Hour 5:30 PM Day 27 Month 12 Year 1973

The above well was plugged as follows:

237'--8 5/8" Surface casing, cement circulated.
3998'--5 1/2" casing cemented on bottom with 450', 2-stage collar set @ 1804' with 150
Cu. Ft. "Stratocrete". (Open Hole Completion).
Squeezed 5 1/2" casing initially with 5 sacks hulls and 25 Sx. cement and followed with
40 sacks gel then 60 Sx. cement. Maximum pump-in pressure-100#. Final shut-in press-
ure-50#. Pressured annulus to 500# with no leakage.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1/4/74

Signed:

A. L. Nichols
Well Plugging Supervisor

INV. NO. 8358-W