

15-065-01676-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 2 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Rocket-Schusterman Oil Account,  
Complete Address 1209 Mid-Continent Building, Tulsa, Oklahoma.  
Lease Name Miller Well No. 5  
Location SW-NE-SW Sec. 3 Twp. 10 Rge. (E) (W) 21  
County Graham Total Depth 3844'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Allied Cementing Company, Incorporated,  
Address Box #207, Russell, Kansas. License No. \_\_\_\_\_  
Operation Completed: Hour 2:30 PM Day 27 Month 12 Year 1973

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3841'--5 1/2" Production casing cemented on bottom. No plug back nor perforations indicated. 5 1/2" casing has been squeezed @ 1210' with 325 Sx. cement.  
Squeezed 5 1/2" casing initially with 3 sacks hulls and 25 Sx. cement then followed with 30 sacks gel and finally 60 Sx. cement. Maximum pump-in pressure-600#. Final shut-in pressure-250#. Pressured annulus to 500# with no leakage.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 1/4/74  
INV. NO. 8357-W