

15-065-01143-0001

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Kern Well No. 3

Location SE-NW-SE Sec. 4 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3876'

Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:00 PM Day 30 Month 6 Year 1970

The above well was plugged as follows:

103'--8 5/8" Surface casing, cement circulated with 60 Sx.  
3874'--5 1/2" casing cemented on bottom with 125 Sx. 5 1/2" had been squeezed @ 1385' with  
150 Sx. cement and @ 1480' with 150 Sx. cement. 4 1/2" liner set @ 1759' with cement  
circulated to surface.

Squeezed well initially with 25 Sx. cement and 15 sacks gel. Pressure rose to 1500#.

Released pressure, ran 1" pipe to 50' and circulated 5 Sx. cement to surface. Tied  
on anulus and squeezed with 7 sacks gel followed with 50 Sx. cement. Maximum pump-in  
pressure-200#. Final shut-in pressure-100#. Checked top of cement in 5 1/2" 7/1/70  
and found it 5' below bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/6/70  
INV. NO. 2172-W  
CONSERVATION DIVISION  
Wichita, Kansas