

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG. 14 1962

CONSERVATION DIVISION  
Wichita, Kansas

08-14-62

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas

Lease Name Kern Well No. 1 Twin

Location NW NW SE Sec. 4 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3871

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 4:30 Day 10 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 104' circulated with cement - 5 1/2" 3869' with 175 sax cement & squeezed at 1200' with 200 sax cement.  
Filled with sand to 3850' set 4 sax cement with dump bailer - pulled 520' 5 1/2" to 500', tried to circulate hole with mud - hole pressured up - pulled pipe to 320', circulated hole with heavy mud, displaced 20 sax cement through 5 1/2" at 320', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 8/15/62  
INV. NO. 5584-W

Signed: Edon Letty  
Well Plugging Supervisor