

15-065-19020-0000

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1962  
CONSERVATION DIVISION  
STATE OF KANSAS

04-12-62

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Graham

Location: SE SE SE Sec. 4 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 21

Name of Field: \_\_\_\_\_ Total Depth: 3868

I have this date completed supervision of plugging of:

Lease Name: Kern Well No. 2

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas

Plugging Contractor Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 9 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 102' circulated with cement - 5 1/2" 3854' with 100 sax cement  
squeezed at 1190' with 200 sax cement - Filled with sand to 3840', set  
4 sax cement with dump bailer.

Pulled 720' 5 1/2" to 500', circulated hole with heavy gel mud at 500' (20 sax  
gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 160', displac  
ed 20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10  
sax cement to bottom cellar.

Mudding and cementing by Company pump truck.

Signed: Edon Perry  
Conservation Division Agent

Reviewed: Harold H. Davis  
Field Supervisor

Remarks:

INVOICED

DATE 4/19/62

INV. NO. 4839-W