

15-065-00392-0007

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1961

CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham
Location: NW SW NW Sec. 4 Twp. 10 Rge. _____ (E) _____ (W) 21
Name of Field: _____ Total Depth: 3941

I have this date completed supervision of plugging of:

Lease Name: Rudman Well No. B-2
Operator's Full Name: Morganstern - Specter
Complete Address: Box 661 Russell, Kansas
Plugging Contractor: Lynch Pipe Pulling Co
Address: Great Bend, Kansas License No. 457

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 28 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 160' circulated with cement - 5 1/2" 3940' with 125 sax cement.
PB with plugs and sand to 3200', set 4 sax cement with dump bailer, pulled
1066' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500'
(15 sax Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to
160', displaced 20 sax cement through 5 1/2" at 160', heavy mud to 40', set
rock bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Lynch Company pump truck.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/17/61
INV. NO. 3577-W