

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG. 1 0.1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co
Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas
Lease Name Long Well No. 1
Location SW SW NE Sec. 4 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3873
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kansas License No. 399
Operation Completed: Hour 4PM Day 8 Month 8 Year 1962

The Above well was plugged as follows:

8 5/8" 134' circulated with cement - 5 1/2" 3871' with 75 sax cement & squeezed in Dakota section with cement at 1180'

Filled with sand to 3850', set 4 sax cement with dump bailer, pulled 850' 5 1/2" to 550', tried to circulate hole with gel mud - hole pressured up - pulled pipe to 450', tried to circulate with mud - hole pressured up - pulled pipe to 400', tried to circulate hole with mud - hole pressured up - pulled pipe to 340', circulated hole with heavy mud (total of 42 sax gel) - Displced 20 sax cement through 5 1/2" at 340' - heavy gel mud to 35', set 10 sax cement to bottom cellar.

Mudding and cementing by Southwest pump truck.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 8/13/62

INV. NO. 5506-W

Signed: [Signature]
Well Plugging Supervisor