

15-065-01139-000P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,
Complete Address 1130 Vickers-KSB&T Building, Wichita, Kansas. 67202
Lease Name Kern Well No. 5
Location W/2-SE-SE Sec. 4 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3873'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Halliburton Services,
Address P. O. Box #339, Hays, Kansas. License No.
Operation Completed: Hour 2:15 PM Day 26 Month 3 Year 1970

The above well was plugged as follows:

118'--8 5/8" Surface casing, cement circulated.
3870'--5 1/2" Production casing cemented on bottom with 100 Sx. 5 1/2" has been squeezed thru leak and is sanded back to 3840' with Frac Sand. No attempt to recover 5 1/2".
Ran measuring line and found top of fluid in 5 1/2" @ 1075'. Squeezed 5 1/2" initially with 5 sacks hulls then 30 sacks gel and followed with 135 Sx. cement. Maximum pump-in pressure--75#. Attempted to pump 15 Sx. cement down annulus between 8 5/8" and 5 1/2". Cement returned into cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3-30-70

INV. NO. 1659-W