

15-065-01699-0000

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
APR 17 1962  
04-17-62  
CONSERVATION DIVISION  
Wichita, Kansas

File No. \_\_\_\_\_ County: Graham

Location: 30' South of  
NW NW SE Sec. 4 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 21

Name of Field: \_\_\_\_\_ Total Depth: 3871

I have this date completed supervision of plugging of:

Lease Name: Kern Well No. 4

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kans

Plugging Contractor Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 11 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 104' circulated with cement - 5 1/2" 3870' with 125 sax cement &  
squeezed with 200 sax cement at 1190' - Lane Walls plug at 3616' - sand  
to 3595' - set 4 sax cement with dump bailer - pulled 605' 5 1/2" to 550'  
circulated hole with heavy mud through 5 1/2" at 550' ( 19 sax Gel), displaced  
20 sax cement through 5 1/2" at 550', heavy mud to 150', displaced 20 sax  
cement through 5 1/2" at 150', heavy mud to 35', cement to 0'  
Mudding and cementing by Company Pump Truck.

Signed: Leon Perry  
Conservation Division Agent

Reviewed: Harold Hobbie  
Field Supervisor

Remarks:

INVOICED  
DATE 4/19/62  
INV. NO. 4838-W