

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: NE NE SW Sec. 4 Twp. 10 Rge. _____ (E) _____ (W) 21

Name of Field: _____ Total Depth: 3871

I have this date completed supervision of plugging of:

Lease Name: Abiram Well No. 23

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kansas License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 11 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 166' circulated with cement - 5 1/2" 3871' with 150 sax cement -

Squeezed in Dakota with cement - Perf 3638'

Filled with sand to 3600', set 5 sax cement with dump bailer, pulled

330' 5 1/2" - circulated mud through 5 1/2" at 330' (20 sax Gel), displaced

20 sax cement through 5 1/2" at 330', heavy mud to 170', displaced 20 sax

cement through 5 1/2" at 170', heavy mud to 35', cement 35' to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edon Beech*
Conservation Division Agent

Reviewed: _____
Field Supervisor

Remarks:

INVOICED
DATE 8/17/61
INV. NO. 3569-W