

15-065-03022-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address: 820 Union National Building, Wichita, Kansas.

Lease Name Abiram Well No. A-1

Location SE-SE-^{SW}~~SE~~ Sec. 4 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3857

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Inc.,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:30PM Day 9 Month 6 Year 1963

The Above well was plugged as follows:

204'--8 5/8" Surface Pipe, cement circulated. 5 1/2" set @ 3852', cemented with 150 Sx. Top perforations from 3600' to 3616'. Well squeezed @ 1180'. Sanded well back to 3590' and set 5 sacks cement with dump bailer. Pulled 5 1/2" to 600' and tried to circulate heavy gel mud. well would not circulate. Pulled 5 1/2" to 300' and pumped in 25 Sx gel and 5 sacks hulls, gained circulation and displaced 20 Sx cement thru casing. Pulled 5 1/2" to 190' and displaced 20 Sx cement thru casing. Pulled 5 1/2", set bridge @ 35' and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/11/63

INV. NO. 7239-W

Signed: H. L. Nichols
Well Plugging Supervisor