

15-065-00314-0000

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CONSERVATION COMMISSION

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

JUN 21 1961  
CONSERVATION DIVISION  
Wichita, Kansas

File No. \_\_\_\_\_ County: Graham

Location: NE NE SW Sec. 4 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 21

Name of Field: \_\_\_\_\_ Total Depth: 3876

I have this date completed supervision of plugging of:

Lease Name: Abiram Well No. 1

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Wichita, Kansas

Plugging Contractor Glenn & Smith

Address: Ellinwood, Kansas License No. 396

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 6 Month 17 Year 61

The above well was plugged as follows:

8 5/8" 134' circulated with cement - 5 1/2" 3872' with 100 sax cement.

Set 5 sax cement on bottom with dump bailer - pulled approx 800' 5 1/2" to

550', circulated hole with heavy mud through 5 1/2" at 550' ( 30 sax Gel),

displaced 20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced

20 sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and filled

to bottom cellar with cement.

Mudding and cementing by Sun Cementing Co.

Signed: Edson Petty  
Conservation Division Agent

Reviewed: Harold Speer  
Field Supervisor

Remarks:

INVOICED

DATE 6/23/61  
3281-W  
INV. NO. 3281-W