

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32334
Name: Chesapeake Operating, Inc.
Address 1: P.O. Box 18496
Address 2: _____
City: Oklahoma City State: OK Zip: 73154 + 0496
Contact Person: Weston Hamilton, Production Engineer
Phone: (405) 935-4594

API No. 15 - 007-20827-0002
If pre 1967, supply original completion date: _____
Spot Description: _____
W2 W2-SW Sec. 6 Twp. 30 S. R. 11 East West
1,320 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Jewell A Well #: 1-6

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" 24# Set at: 251' Cemented with: 252 Sacks
Production Casing Size: 4-1/2# 10.5# Set at: 2,839' Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Wreford: 2,309'-2,318' ; Red Eagle: 2,618'-2,624' ; Indian Cave: 2,748' - 2,778' / no Bridge Plugs

Elevation: 1,847' (G.L. / K.B.) T.D.: 2,840' PBTD: 2,806' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

See Attached Procedure

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

RECEIVED
OCT 30 2009
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Bud Neff, Production Superintendent

Address: 4532 W. Jones Avenue City: Garden City State: KS Zip: 67846 + _____

Phone: (620) 277-0803

Plugging Contractor License #: 99996 Name: Allied Cementing Co., Inc.

Address 1: P.O. Box 31 Address 2: _____

City: Russell State: KS Zip: 67665 + _____

Phone: (785) 483-2627

Proposed Date of Plugging (if known): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent Weston Hamilton

Date: 10/26/09 Authorized Operator / Agent: _____

(Signature)

Digitally signed by Weston Hamilton
DN: dc=net, dc=chkenergy, ou=Users and Groups,
cn=Weston Hamilton, email=weston.hamilton@chk.com
Date: 2009.10.23 09:06:08 -05'00'

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Jewell A 1-6
Plug and Abandon
10-6-09

Procedure:

1. Notify KCC District 1 at least 5 days before commencement of plugging operations.

KCC District 1 – (620)225-8888

2. MIRU WOR. Unhang rods, longstroke pump to check for tubing integrity, release pump & TOOH w/ rods & pump laying down.
3. ND WH, NU BOP, TOOH w/ 91 jts 2-3/8" TBG standing back.
4. PU setting tool and 4-1/2" 10.5# CIBP. TIH w/ CIBP on 2-3/8" TBG and set at \pm 2,255'. MIRU cement company, pump 5 sx cement w/ 2% CaCl₂ on top of CIBP for a 55' plug (Plug 1). TOOH w/ TBG while circulating plugging mud and stand back.
5. RU to pull 4-1/2" CSG and weld on pull nipple, PU on casing, MIRU WLU and RIH w/ tools to locate freepoint, POOH, RIH w/ tools and cut CSG above freepoint (450' is target cut point), POOH, RDMO WLU. TOOH w/ 4-1/2" CSG laying down.
6. TIH w/ 2-3/8" TBG, pump the following balanced plugs in casing/open hole:

Plug 2:	500'-200' Stub and Shoe Plug	90 sx w/ 2% CaCl ₂
	(50' in stub, 199' in open hole, 51' in surface CSG)	
Plug 3:	34'-4' Surface Plug	10 sx w/ 2% CaCl ₂

*Must tag plug 2 w/ tubing to verify top depth as specified

7. Cut off casing 4 ft. below ground level and weld on steel ID plate. RDMO WOR and cement company.
8. Remove all remaining production equipment and restore well site to its original condition.

RECEIVED
OCT 30 2009
KCC WICHITA



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHESAPEAKE OPERATING, INC.
6200 N WESTERN AVE
PO BOX 18496
OKLAHOMA CITY, OK 73118-1046

November 05, 2009

Re: JEWELL A #1-6
API 15-007-20827-00-02
6-30S-11W, 1320 FSL 330 FWL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after May 4, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888