

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5920
Name: TE-PE OIL & GAS
Address 1: P.O. BOX 522
Address 2: _____
City: CANTON State: KS Zip: 67428 + 0 5 2 2
Contact Person: TERRY P BANDY
Phone: (620) 628-4428

API No. ~~25~~ - 15-159-19196-00-01
If pre 1967, supply original completion date: 1948 OWWO 11/76
Spot Description: C SW SW SE
C - SW - SW - SE Sec. 1 Twp. 20 S. R. 6 ☐ East ☒ West
339 Feet from ☐ North / ☒ South Line of Section
2,405 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: RICE
Lease Name: J W BRADEN C Well #: 1

Check One: ☐ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic ☐ Water Supply Well ☐ Other: _____
☒ SWD Permit #: D-18642 ☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8 Set at: 140 Cemented with: 90 Sacks
Production Casing Size: 5-1/2 Set at: 3315 Cemented with: 75 Sacks

List (ALL) Perforations and Bridge Plug Sets:

11/76 OWWO 5-1/2" Set @2179', cmtd w 600 sks.(Tied into old 5-1/2 casing) 10/6/00 4-1/2" liner @1665'k.b.
cmtd w 200 sks. Circ to surface w cmt 4-1/2 X 5-1/2 annu & 5-1/2 X 8-5/8 annu. Perfs 1690-2210

Elevation: 1553 (☒ G.L. / ☐ K.B.) T.D.: 2750 owwo PBTD: 2241owwo Anhydrite Depth: 795
(Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Junk in Hole ☐ Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

To plug according to the rules and regulations of the Kansas Corporation Commission.

Is Well Log attached to this application? ☒ Yes ☐ No Is ACO-1 filed? ☒ Yes ☐ No

If ACO-1 not filed, explain why:

RECEIVED

NOV 10 2009

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Terry P Bandy

Address: P.O. Box 522 City: Canton State: Ks Zip: 67428 + 0 5 2 2

Phone: (620) 628-4428

Plugging Contractor License #: 3038 Name: Cyclone Well Service, Inc.

Address 1: P.O. Box 522 Address 2: _____

City: Canton State: Ks Zip: 67428 + 0 5 2 2

Phone: (620) 628-4428

Proposed Date of Plugging (if known): 11/10/09

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/9/09 Authorized Operator / Agent: _____

 

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

TE-PE OIL & GAS
P.O. BOX 522
CANTON, KANSAS 67428

BRADEN #C-1
SW SW SE SEC 1-20S-6W
RICE COUNTY, KS
DOCKET # D-18,642

7/9/48

Drilled new well. 8-5/8" set at 140', cemented with 90 sacks.
5-1/2" set at 3315', cemented with 75 sacks. Open hole Mississippi.
3315'-3347' oil well completion.

5/24/68

Well was plugged. Pulled 2179' of 5-1/2" casing.

11/4-12/76 OWWO

Wash down and tie onto top of old 5-1/2" casing at 2179', cement with 600 sacks of cement. Drill cement and drill out to 2750' where casing had also been shot to pull in 1968. Squeeze with 200 sacks of cement at 2750'. Drill cement to 2373', hit iron and couldn't get any deeper.

11/19/76

Log well TD 2241'. Perforate 2210-2190, 2074-80, 1980-90, 1792-1802, 1706-10, 1690-94. Run packer and tubing, MIT, put on injection.

10/6/00

Well fails MIT. Run 4-1/2" liner to 1652', cement with 250 sacks. Cement circulated to top on 4-1/2 X 5-1/2 annulus and 5-1/2 X 8-5/8 annulus. Allied cementing ticket #4298. Drill shoe and clean out to 1993'. Hard bottom there, record shows 2 joints of tubing and packer lost in hole previously. Run packer and 2-1/2" duoline to 1618', MIT well. Place back on injection.

5/11/06

Te-Pe Oil & Gas MIT passed. OK.

RECEIVED
NOV 10 2009
KCC WICHITA



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BANDY, TERRY P. DBA TE-PE OIL & GAS
PO BOX 522
CANTON, KS 67428-0522

November 16, 2009

Re: J W BRADEN C #1
API 15-159-19196-00-01
1-20S-6W, 339 FSL 2405 FEL
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after May 15, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000