

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 33719⁸⁵
Name: Energy Operations Kansas, LP
Address 1: 1001 Fannin St
Address 2: Ste 3700
City: Houston State: TX Zip: 77002 +
Contact Person: George Fenati
Phone: (713) 574-4520

API No. 15 - 069-20291 - 0000
If pre 1967, supply original completion date: _____
Spot Description: _____
SW SW SW Sec. 10 Twp. 29 S. R. 30 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Gray
Lease Name: Copeland Well #: 1-10

Check One: Oil Well Gas Well ~~OG~~ Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: 20" Set at: 42' Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1782' Cemented with: 675 Sacks
Production Casing Size: 5 1/2" Set at: 5155' Cemented with: 200 DV Tool @ 3176'w/ 200 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Perfs: 5022-5030 4 spf; 4886-4902' 3 spf; 2690-2700, 2720-2738 3 spf;
Existing Bridge Plugs: 5000' + 2 sxs; 4870' + 2 sxs

Elevation: 2818' (G.L. / K.B.) T.D.: 5574' P.B.T.D.: 5110' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

CIBP @ 2640' w/ 2 sks cement. Load csg w/ mud & pull 4 1/2" free pipe. Run tbg @ 1832' & spot 100 sks cement. Tag TOC (1732' or higher) . Run tbg @ 770' & spot 50 sks . Top out 34' - 4' w/ 10 sks

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

**RECEIVED
NOV 12 2009**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

KCC WICHITA

Company Representative authorized to supervise plugging operations: Rob Patterson
Address: 25335 C.R. DD5 City: Springfield State: CO Zip: 81073 +
Phone: (972) 367-0535
Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: OK Zip: 73534 + 1706
Phone: (580) 467-0258
Proposed Date of Plugging (if known): 11/09/2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 11/5/09 Authorized Operator / Agent: George Fenati
(Signature)

*Dist 1
OK*



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ENERGY OPERATIONS KANSAS, LP
1001 FANNIN ST, STE 3700
HOUSTON, TX 77002

November 16, 2009

Re: COPELAND #1-10
API 15-069-20291-00-00
10-29S-30W, 330 FSL 330 FWL
GRAY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after May 15, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888