

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Ellis County. Sec. 28 Twp. 12 Rge. (E) 19 (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW SW SE  
Lease Owner: Hendon Dr-16. Co.  
Lease Name: Pelzano Well No. 1  
Office Address: Box 489 Tulsa Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed..... 19.....  
Application for plugging filed 6-1- 1950  
Application for plugging approved 6-1- 1950  
Plugging commenced 6-1- 1950  
Plugging completed 6-1- 1950  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production..... 19.....  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 387 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8 5/8</u>	<u>195</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Filled hole with heavy mud to 180 ft. Placed plug at 180 ft. Placed 15 sacks of cement on top of plug filled with heavy mud to 30 ft. Placed plug @ 30 ft. filled with cement to bottom of cellar.

Rec'd 6-8-50

(If additional description is necessary, use BACK of this sheet.)  
Correspondence regarding this well should be addressed to Hendon Dr-16 Co  
Address Box 489 Tulsa Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.  
(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. S. Guther

SUBSCRIBED AND SWORN to before me this 6<sup>TH</sup> day of JUNE, 1950

My commission expires Sept 19, 1950  
John Myers Notary Public.

22-237 7-47-10M  
FILE SEC 28 T 12 R 19  
BOOK PAGE 9 LINE 26

# 31

15-051-00507-00-00

WELL LOG ON PIERANO #1

Spudding date: 5-11-50  
Date casing set: 6-1-50 Plugged  
Date rotary completed: 5-22-50  
Date cable completed:

Location: Section 28-12S-19E, Ellis County, Kansas

FROM	TO	FORMATION	REMARKS
0	195	Shale and clay	Ran 5 Jts. 200' 8 5/8" spiral-weld Csg., set @ 195' W/ 125 Sx, 200# C. C.
195	1435	Shale and shells	
1435	1585	Lime and shale	
1585	2000	Lime	
2000	2200	Lime and shale	
2200	2325	Lime	
2325	3175	Lime and shale	
3175	3265	Lime	
3265	3316	Lime and shale	
3316	3510	Lime and chert	
3510	3805	Lime	
3805	3850	Conglomerate	
3850	3878	Lime - T. D. - Plugged	

RECORDED

6-8-1950  
JUN 8 X 1950

STATE OF KANSAS  
COMMISSIONER OF GEOL. & MIN.

Subscribed and sworn to before me this 6th day of June, 1950

I certify the above and foregoing to be a true and exact copy of the original driller's log on the Pierano #1

Ernest Steger  
Notary Public  
My commission expires: Aug. 28, 1951

HERNDON DRILLING COMPANY  
By: [Signature]  
Title:

PLUGGING  
FILE SEC 28 T. 12 R. 19E  
BOOK PAGE 9 LINE 26