

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

15-051-24505-00-00
WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24505

LEASE NAME Crathorne

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 29 TWP. 12 RGE. 19 ~~XXXXX~~ (W)

COUNTY Ellis

Date Well Completed 9-18-87

Plugging Commenced 9-18-87

Plugging Completed 9-18-87

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS Rt. 1, Box 183-B, Great Bend, KS 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6 - Hays

Is ACO-1 filed? will be by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3879'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plug #1 set at 3847' with 255 sacks cement through drill pipe
Plug #2 set at 1525' with 255 sacks cement through drill pipe
Plug #3 set at 820' with 100 sacks cement & 1 sack seal flake through drill pipe **See Reverse Side
Plug #5 set at 40' with 10 sacks cement 15 sacks in rat hole
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address PO Box 877, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors


(Address) PO Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28 day of September, 19 87

Dorothy M. Hague
Notary Public

STATE CORPORATION COMMISSION

My Commission Expires: 5-5-90



9-29-1987
SEP 29 1987 Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas

Plug #4 set at 310' with 40 sacks cement through drill pipe

15-051-24505-00-00
DRILLERS WELL LOG

DATE COMMENCED: September 12, 1987
DATE COMPLETED: September 18, 1987

Davis Petroleum, Inc.
Crathorne #1
N/2 NW NE
Sec. 29-12-19W
Ellis County, Kansas

0 - 1510 Surface Soil, Sand, Shale
1510 - 1554 Anhydrite
1554 - 3446 Shale, Lime
3446 - 3450 Shale
3450 - 3487 Lime Shale
3487 - 3726 Lime
3726 - 3847 Shale, Lime
3847 - 3879 Dolomite
3879 RTD

ELEVATION: 2176'

FORMATION DATA

Anhydrite	1510-1554
Heebner	3446
Lansing	3487
Base K.C.	3726
Arbuckle	3847

Surface Pipe: Set new 8-5/8"
at 260' with 150 sacks 60/40
pozmix, 2% gel, 3% c.c.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 28 day of September, 1987.



Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
9-29-1987
SEP 29 1987

CONSERVATION DIVISION
Wichita, Kansas