


15-051-30296-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 29 Twp. 12 Rge. 19 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE-SW-NE  
Lease Owner Joe Furthmyer  
Lease Name Crathorne Well No. 1  
Office Address Gorham, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 3-28-1966  
Application for plugging filed 3-28-1966  
Application for plugging approved 3-28-1966  
Plugging commenced 3-28-1966  
Plugging completed 3-28-1966  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey-Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3570' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	218'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sax cement. Filling hole with rotary mud to a depth of 210' where 2nd plug was set using 20 sax cement. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sacks cement and filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
3-31-1966  
MAR 31 1966

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Victoria, Kansas

STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
LEO F. DREILING (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 19 66

My commission expires October 26, 1968

Elmer Weitz  
Elmer Weitz Notary Public.

15-051-30296-00-00

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company Joe Furthmyer  
Gorham, Kansas

Sec. 29 Twp. 12 Rng. 19

Farm Crathorne No. 1

Location SE-SW-NE

Total Depth 3570'

County Ellis

Comm. 3-2-66 Comp. 3-28-66

Elevation: D. F. 2182  
K. B. 2179  
G. R. 2177

Contractor

Casing Record  
218' 8-5/8"

Cement Record  
150 sax Sunset

Production:  
D & A

Figures Indicate Bottom of Formations

0'	30'	Surface Soil
30'	500'	Post Rock
50'	218'	Shale
218'	343'	Shale
343'	975'	Shale
975'	1193'	Sand
1193'	1513'	Red Bed & Shale
1513'	1559'	Anhy.
1559'	1565'	Shale
1565'	2160'	Shale & Shells
2160'	2525'	Shale & lime
2525'	2845'	Shale & Lime
2845'	3044'	Lime & Shale
3044'	3309'	Lime & Shale
3309'	3432'	Lime & Shale
3432'	3526'	Lime
3526'	3570'	Lime
3570'	T.D.	

STATE OF KANSAS )  
                          )ss  
COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L.J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Crathorne # 1.

*Leo F. Dreiling*  
\_\_\_\_\_  
LEO F. DREILING

Subscribed and sworn to before me this 29th day of March, 1966.

*Emmer Feltz*  
\_\_\_\_\_  
NOTARY PUBLIC

My commission expires: October 26, 1968

3-31-1966