

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: BP AMERICA PRODUCTION COMPANY

Address: P.O. BOX 3092, Rm 6.192, HOUSTON, TX 77253

Phone: (281) 366-4395 Operator License #: 5952

Type of Well: GAS Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: July 07, 2009 (Date)

by: STEVE DURRANT (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Council Grove Depth to Top: 2836 Bottom: 2944 T.D. 3003

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15- 093-20701 - 0000

Lease Name: Rohlman 'A'

Well Number: #2

Spot Location (QQQQ): - - C - NW

3960 Feet from North / South Section Line

3960 Feet from East / West Section Line

Sec. 35 Twp. 23S S. R. 38W East West

County: KEARNY

Date Well Completed: 10-24-80

Plugging Commenced: 08-19-09

Plugging Completed: 08-19-09

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Rows include SURFACE CASING and PRODUCTION CASING.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

08/19/2009-SEE ATTACHED REPORT.

RECEIVED

OCT 09 2009

KCC WICHITA

Name of Plugging Contractor: ORR ENTERPRISES, INC. License #: 33338

Address:

Name of Party Responsible for Plugging Fees: BP AMERICA PRODUCTION COMPANY

State of TEXAS County, HARRIS, ss.

DEANN SMYERS (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Deann Smyers

(Address) P.O. BOX 3092, RM 6.192, WL-1 HOUSTON, TX 77253-3092



SUBSCRIBED and SWORN TO before me this 31st day of August, 2009. Suzanne M. Jones, Notary Public. My Commission Expires: 1-11-2013

## Hotnotes Report

Legal Name: ROHLMAN GAS UNIT /A/ /CG/ 002  
 Common Name: ROHLMAN GAS UNIT /A/ /CG/ 002  
 Country: UNITED STATES  
 API #: 1509320701 Well ID: 840471 State/Prov: KANSAS County: KEARNY  
 Location: 35- 23-S 38-W 1  
 Field Name: PANOMA  
 Block: Slot No: 84 Platform:  
 License No: License Date: Licensee:  
 Spud Date/Time: 10/24/1980 - : P&A Date: 8/19/2009

Date	Reason	Description
8/19/2009	CHANGE OF SCOPE	<p>           1. TIH WITH TUBING TO 2700'.            2. MIX AND PUMP 50 SACKS OF CLASS C CEMENT W/2% CALCIUM CHLORIDE &amp; 100 LBS OF COTTONSEED HULLS &amp; 2% GEL TO SET PLUG FROM 2944' TO 2150'.            3. PULL TUBING TO 2000'. WOC 2 HRS            4. MIX AND PUMP 90 SACKS OF CEMENT WITH 2% BENTONITE WITH 100 LBS OF COTTONSEED HULLS TO FILL CASING FROM 2000' TO 1000'.            5. PULL TUBING TO 1000'.            6. MIX AND PUMP 80 SACKS OF CEMENT TO FILL CASING FROM 1000' TO 0'.            7. TOH WITH TUBING.            8. TOP OFF CASING WITH 5 SACKS OF CEMENT.            9. MIX AND PUMP 8 SACKS OF CEMENT TO FILL 8 5/8" X 5 1/2" ANNULUS.            10. CUT OFF AND CAP CASING 5' BELOW GROUND LEVEL.            11. RESTORE THE LOCATION.         </p> <p>           CEMENT BLEND: CLASS "C" CEMENT WITH 2% GEL MIXED AT 13.5 PPG WITH A YIELD OF 1.51 CUFT/SK.            TOTAL CEMENT: 225 SACKS INSIDE 5 1/2" CASING.            8 SACKS IN ANNULUS.         </p> <p>           PLUGGING PROGRAM APPROVED BY STEVE DURRANT WITH THE KCC            PLUGGING JOB PUMPED BY ORR ENTERPRISES, INC            PLUGGING JOB WITNESSED BY JACK MACLASKEY WITH THE KCC            PLUGGING JOB SUPERVISED BY ROD KAPP AND KEVIN STRUBE WITH BP         </p> <div style="text-align: right; margin-top: 20px;"> <p>RECEIVED</p> <p>OCT 09 2009</p> <p>KCC WICHITA</p> </div>