

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LaVeta Oil & Gas, LLC

Address: 312 N. Buffalo, Stafford, KS 67578

Phone: (620) 786-8072 Operator License #: 32432

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: ¹⁸⁵ 15-186-21289-00-02

Lease Name: Komarek

Well Number: #22

Spot Location (QQQQ): SW SE
321 Feet from North / South Section Line KCC
1275 Feet from East / West Section Line pen
30 Sec. 22 Twp. 11 S. R. East West CP 2/3

County: Stafford

Date Well Completed: _____

Plugging Commenced: 09/17/09

Plugging Completed: 09/23/09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | | | |
| | | | | 8 5/8" | 552' | |
| | | | | 5 1/2" | 3,543' | 2,020' |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Had bridge plug at 2,800'. Bailed 5 sacks cement with bailer. Pulled slips; Had 18" stretch. Ripped casing at 2,250'; Tried to fish knife; Fished knife out of hole. Worked casing; Left tension on. Ripped casing at 2,020'. Pulled casing up to 580'; Pumped 10 gel and 50 sacks 100# hulls. Well didn't circulate; Pulled up to 250'. KCC wanted to tag plug at 580'. Tagged cement at 480'; Pumped 40 sacks at 250'. Pulled to 40'; Pumped 20 sacks to surface.


Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: LA Veta Oil & Gas

State of _____ County, _____, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Marten Ziegler contact agent

(Address) 312 N. Buffalo

SUBSCRIBED and SWORN TO before me this 10th day of October, 2009

Katharine M. Sipes My Commission Expires: August 10, 2011
Notary Public