

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

OCT 05 2009

Form CP-4 March 2009

Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 31790 Name: FREMONT EXPLORATION, INC. Address 1: 12412 St. Andrews Dr. Address 2: City: Oklahoma City State: OK Zip: 73120 Contact Person: Tom Conroy Phone: (405) 936-0012 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): LKC Depth to Top: 3796 Bottom: 3800 T.D. 3870

API No. 15 - 065-22570 - 0000 Spot Description: C W2 SE SW Sec. 27 Twp. 7 S. R. 23 East West 660 Feet from North South Line of Section 1,650 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: GRAHAM Lease Name: MORRIS Well #: 1-27 Date Well Completed: 6-9-90 The plugging proposal was approved on: 09-09-09 (Date) by: Pat Balthazor (KCC District Agent's Name) Plugging Commenced: 9-09-09 Plugging Completed: 9-09-09

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: LKC 3796' - 3800', Oil & water, Surface, 8 5/8", 213, NONE. Row 2: Production, 4 1/2", 3854, NONE.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP set @ 3500'. Run tubing to 3000', spot 150 sx 60/40 POZ w/4 % gel & 200# hulls. Pulled tubing to 14889', mix & pump 75 sx 60/40 POZ w/1000# hulls. Cement circulated to surface. Pull tubing out of hole. Put 4 1/2" swedge on casing, pump 15 sx, pressure to 700#. Dug out braden head and pumped 10 sx between 4 1/2" & 8 5/8", pressured to 300#. Cut off 4 1/2" & 8 5/8" below ground and back-filled.

KCC PKT per CP 2/3 Whitetail Crude Inc

Plugging Contractor License #: NA 31627 Name: Allied Cementing Co., Inc.

Address 1: P.O. Box 31 Address 2:

City: Russell State: KS Zip: 67665

Phone: (785) 483-3887

Name of Party Responsible for Plugging Fees: Fremont Exploration, Inc.

State of Oklahoma County, Oklahoma, ss.

Tom Conroy (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tom Conroy

PKT