

API NUMBER 15-163-21,677-0000

LEASE NAME SUTOR

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #12

2310 Ft. from S Section Line

330 Ft. from E Section Line
2310 AMB LCC

SEC. 22 TWP. 10 S RGE. 20 (W)

LEASE OPERATOR Champlin Petroleum CO.

ADDRESS 1441 N. GRAND BLVD. STE. 300 OKLA CITY OKLA 73116 COUNTY ROOKS

PHONE#(405) 840 5521 OPERATORS LICENSE NO. 6417

Date Well Completed 8/12/82

Character of Well oil

Plugging Commenced 4/4/84

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/5/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lindsay & Arbuckle Depth to Top 3530 Bottom 3772 T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	226	NONE
				5 1/2	3899	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Hook up Howco To 8 5/8" & 5 1/2" Annulus. Mix & pump 4 SKS ECONOLITE Cement & 1/4# Floccle 1 SK. pressure to 600# & shut in. Hook up to 5 1/2" casing mix & pump 160 SKS cement down casing w/ 5 SKS HULLS in first 30 SKS cement. casing filled w/ 88 BAIS. pressure 1200# w/ 100 BAIS. SI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Holliburton Services License No. _____

Address Hays Kansas

STATE OF OKLA COUNTY OF OKLA., ss.

Steve Harwell (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed that the same are true and correct, so I hereby certify.

(Signature) Steve Harwell

(Address) 1441 N. GRAND BLVD. OKLA-CITY OKLA.

APR 23 1986

SUBSCRIBED AND SWORN to before me this 22 day of April, 19 86

Debbie S. Douglas
 Notary Public

My Commission Expires: 06-21-88