

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 5 Twp. 12 S Rge. 20 (W) (W)

Location as "NE/CNW&SW&" or footage from lines NW NW NW

Lease Owner Halliburton Estate - Sierra Petroleum - Contr. & Opr

Lease Name DEUTSCHER Well No. 1

Office Address Okla City, Okla. - 208 Petroleum Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 3/23/58 19__

Application for plugging filed 3/23/58 19__

Application for plugging approved 3/23/58 19__

Plugging commenced 3/24/58 19__

Plugging completed 3/24/58 19__

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3950 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	282	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 3950 up to 650'. Set bridge with 1/3 sack hulls, wood plug and 20 sks cement through drill pipe. Filled hole with mud up to 270'. Set bridge, 1/3 sks hulls, wood plug and 15 sacks cement through drill pipe. Filled hole with heavy mud up to 40'. Set bridge with 1/3 sks hulls, wood plug and 10 sacks cement to cellar 0. Job completed 1:00 a.m. 3/24/58

326-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.

Address 208 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.

C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address) _____

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 58

Margie Cooper
Notary Public.

My commission expires 1-30-61.

PLUGGING
FILE SEC 5 T. 12 R. 20
BOOK PAGE 90 LINE 24

15-051-01186-00-00

Earl P. Halliburton Est - Owner

Sierra Petroleum - Operator

DEUTSCHER #1

NW NW NW Sec. 5-12S-20W
Ellis County, Kansas

Total Depth: 3950

Elev: 2257 KB

Comm: 3/12/58

Comp: 3/23/58

Casing:

8 5/8 @ 282

Cement:

with 150 sacks cement

FORMATION	DEPTH
Surface clay & sand	70
Sand & shale	125
Shale & shells	282
Shale	500
Shale, shells & sand	775
Shale, shells & red bed	1200
Sand, shale & shells	1440
Red bed & shale	1670
Anhydrite	1715
Shale & shells	2000
Shale, shells & salt	2175
Shale & lime	3564
Lime	3932
Arbuckle	3950
Tops:	
Anhydrite	1670
Topeka	3301
Heebner	3525
Toronto	3542
Lans. K. C.	3563
Congl.	3835
Arbuckle	3922

STATE OF KANSAS)
COUNTY OF RUSSELL) ss:

I hereby certify that the above information is true and correct to the best of my knowledge.

C. D. Henker

Subscribed and sworn to before me this 24th day of March, 1958.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

3-26-1958

PLUGGING
FILE SEC 5-T-12 R-200
BOOK PAGE 90 LINE 24