

15-051-01186-00-01

API NUMBER _____

LEASE NAME Calvert/Deutscher 1

WELL NUMBER 1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 5 TWP. 12 RGE. 20 (E) or (W)

COUNTY Ellis

Date Well Completed 5/31/73

Plugging Commenced 8/2/96

Plugging Completed 8/2/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Bennett & Schulte Oil Company

ADDRESS P.O. Box 329 Russell, KS 67665

PHONE# (913) 483-2721 OPERATORS LICENSE NO. 6246

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/2/96 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	282	None
				5 1/2	3822	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Perf 1690. Tubing to 1689 & Spot 50 sx cement w/150# hulls. Pulled tubing to 915 & perf @925 mix 65 sx cement w/150# hulls & cement circulated cement to surface. 5 1/2 csq. swage squeezed 45 sx w/200# hulls & cement circ around annulus. Shut in and mixed another 55 sx cement & 700# shut in @ 500#. Used 215 sx cement

Name of Plugging Contractor Bennett & Schulte Oil Company License No. 325

Address P.O. Box 329 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bennett & Schulte Oil Company

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Frank Schulte (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Frank R. Schulte*

(Address) P.O. Box 329 Russell, KS 67665

12-30-1996
 9661-08-21

SUBSCRIBED AND SWORN TO before me this 26 day of December, 1996

Notary Public

My Commission Expires: _____