


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-051-00649-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Ellis County, Sec. 5 Twp. 12 Rge. (E) 20 (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE SE  
Lease Owner Herndon Drilling Company  
Lease Name HAMBURG Well No. 1  
Office Address Mayo Building (Drawer 489), Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed August 4 19 51  
Application for plugging filed August 4 19 51  
Application for plugging approved August 4 19 51  
Plugging commenced August 4 19 51  
Plugging completed August 4 19 51  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	195'	8-5/8	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud to 190'. Wooden plug pushed to 190' with drill pipe. Mixed 15 sacks cement and poured on top of plug. Filled hole with mud to 40'. Pushed plug to 40'. Mixed 10 sacks cement. Filled last 40' to bottom of cellar which is 4' below ground level



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Herndon Drilling Company  
Address Drawer 489, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa  
Jack Herndon (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Mayo Building, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of September 19 51  
[Signature] Notary Public.

My commission expires Sept. 19, 1952  
23-8390-s 6-51-20M

PLUGGING  
FILE SEC STLYR 200  
BOOK PAGE 601 LINE 31

15-051-00649-00-00

WELL LOG ON HAMBURG #1

Spudding date: 7-24-51

Date casing set: D & A

Date rotary completed: 8-4-51

Date cable completed:

Location:

SE SE SE Sec. 5-12S-20W  
Ellis County, Kansas

FROM	TO	FORMATION	REMARKS
0	245	Shale and white rock	Ran 11 jts. (244.52') of used 8-5/8" Csg. at 244' w/150 Sx. cement and 200# C. C.
245	990	Shale and shells	
990	1045	Sand	
1045	1080	Shale and shells	
1080	1356	Sand	
1356	1675	Shale and shells	
1675	1715	Anhydrite	
1715	1865	Shale	
1865	2241	Shale and shells	
2241	2540	Shale and lime	
2540	2650	Shale and shells	
2650	3660	Shale and lime	
3660	3670	Chert and lime	
3670	3727	Shale and lime	
3727	4086	Lime	
4086		TOTAL DEPTH	Plug at 225' w/15 Sx. cement Plug 40' to surface w/10 Sx. cement.

RECEIVED  
 9-6-1951  
 SEP 6 X 1951  
 COMMISSION  
 DIVISION  
 Kansas

Subscribed and sworn to before me this 10th  
 day of August, 1951

I certify the above and foregoing to be a true and exact  
 copy of the original driller's log on the Hamburg #1

Ernest Morgan  
 Notary Public  
 My commission expires:

HERNDON DRILLING COMPANY  
 By: C. Moore  
 Title:

My commission expires Aug. 28, 1953

PLUGGING  
 FILE SEC 5 T 12 R 20W  
 BOOK PAGE 101 LINK 37