

15-051-20222-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
3-18-1968  
MAR 18 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address: 1425 Wichita Plaza Wichita, Kansas

Lease Name Urban Well No. 1

Location SW NW SW Sec. 5 Twp. 12 Rge. 20 (E)      (W) X

County Ellis Total Depth 3983

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 2:15 A Day 17 Month 3 Year 1968

The Above well was plugged as follows:

RTD 3983' 8 5/8 csg set at 241' cwc 150 sc. Cem. Mat. 50-50 poz cement W/6% gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INDEXED  
DATE 3/18/68  
INV. NO. 7434-U