

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION  
5-1-1962  
MAY 1 1962

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: CSW NE Sec. 5 Twp. 12 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 20  
Name of Field: \_\_\_\_\_ Total Depth: 4000

I have this date completed supervision of plugging of:

Lease Name: Trion Well No. 1

Operator's Full Name: J. O. Farmer Inc

Complete Address: Russell, Kansas

Plugging Contractor Forbes Casing Pulling

Address: Great Bend, Kans License No. 49

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A x

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No x

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 28 Month 4 Year 62

The above well was plugged as follows:

8 5/8" <sup>160'</sup> ~~200'~~ circulated with cement - 4 1/2" 3998' with 100 sax cement, perf 3896'  
PB with sand to 3850', set 4 sax cement with dump bailer, pulled 3210' 4 1/2"  
to 550', circulated hole with heavy mud through 4 1/2" ( 35 sax Gel), displaced  
20 sax cement through 4 1/2" at 550', heavy mud to 160', displaced 20 sax cement  
through 4 1/2" at 160', heavy mud to 35', cement 35' to 0'.

Mudding and cementing by Halliburton Co.

Signed: Edwin Peety  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

**INVOICED**  
DATE 5/11/62  
INV. NO. 4936-W