

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Frontier Oil Co.

Complete Address 1437 N. Franklin, Russell, Kansas 67665

Lease Name Raymond Well No. 1

Location SW SW SW Sec. 24 Twp. 12 Rge. (E) (W) 20

County Ellis Total Depth 3881'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 10:45 A Day 30 Month 8 Year 1978

The above well was plugged as follows:

8-31-1978

Total Depth 3881' 8 5/8 csg set 258' cwc 160 sk.

4 1/2 csg set 3861' cw 150 sk cem.

Filled 4 1/2 csg W/sd (3881'-3830') dumped 3 sk cem W/dump bailer. (3830'-3800')

Cutoff & recovered 3000' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs

hulls, followed with 70 sk 50-50 poz 6% -displaced with 8 sk gel & water & capped

with cementing plug & 50 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 8-31-78

INV. NO. 7971-W