

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-15-1964
JAN 15 1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Pet Co

Complete Address: Box 287 Great Bend, Kansas

Lease Name Staab Well No. 1

Location CSE SE Sec. 23 Twp. 12 Rge. (E) (W) 20

County Ellis Total Depth 3962

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Inc

Address: Chase, Kansas License No. 436

Operation Completed: Hour 5:30PM Day 9 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 300' circulated with cement - 4 1/2" 3962' with 100 sax cement
PB to 3912* Perf 3879' - 3817' & 3525' - set plug at 3500' - sand and
3 sax cement set with dump bailer.

Pulled 3109' 4 1/2" to 575' - circulated hole with heavy gel mud through
4 1/2" at 575' (21 sax Gel), displaced ~~was~~ 20 sax cement through 4 1/2" at
575', heavy gel mud to 200', displaced 20 sax cement through 4 1/2" at
200', heavy gel mud to 35', cement to bottom cellar.

Mudding and cementing by King Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/15/64
INV. NO. 8467-W

Signed: [Signature]
Well Plugging Supervisor