

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-2-1978
OCT - 2 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
(of this well)
Wichita, Kansas

Operator's Full Name Frontier Oil Co.
Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202
Lease Name Stabb Well No. 1
Location SE SE SE Sec. 23 Twp. 12 Rge. (E) (W) 20
County Ellis Total Depth 3896'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering, Inc.
Address Box 698, Great Bend, Kansas 67530 License No. 670
Operation Completed: Hour 10:45 A Day 29 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3896' 8 5/8 csg set 284' cwc 180 sk.
4 1/2 csg set 3883' cw 165 sk cem. Top perf. (3800')
Filled 4 1/2 csg W/sd (3896'-3875') dumped 4 sk cem W/dump bailer. (3775'-3745')
Cutoff & recovered 3100' of 4 1/2 csg.
Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -followed
with 70 sk 50-50 poz 2% - displaced with 8 sk gel & water & capped with 70 sk
50-50 poz 2% & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-4-78

INV. NO. 8197-W

Signed: R. Co. Massey
Well Plugging Supervisor