

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,980

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name R.P. Nixon Operations

Complete Address 207 W. 12th, Hays, Ks. 67601

Lease Name Staab "A" Well No. 1

Location SW SE SE Sec. 23 Twp. 12 Rge. 20 (East) (West)

County Ellis Total Depth 3926'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524

License No.

Operation Completed: Hour: 2:00 PM Day: 9 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part None

The above well was plugged as follows:

8 5/8"-190' S.P. cUc. w/140 sacks common cement. 4 1/2" set at 3925' w/125 sacks
Common cement. Top perf. at 3285'. Pushed plug to plug off bottom to 3200' w/50'
of sand & 4 sacks cement. Shot pipe time & recovered 3023'. Ordered 165 sacks
50/50 posmix-4% gel.-3% Cal.Cl., 20 sacks Gel., 5 sacks hulls & 8 5/8" plug.
Pumped into 8 5/8" S.P. w/pump truck, 4 sacks hulls, 25 sacks cement, 15 sacks Gel.
70 sacks cement, 5 sacks Gel., 1 sack hulls, released plug & followed w/70 sacks
cement. Maximum pressure 200 pounds.

Amount of Surface Casing: 190' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

~~_____

_____~~

RECEIVED
STATE CORPORATION COMMISSION
7-12-1982
JUL 12 1982

Signed: _____
Conservation Division Agent

7-13-82
621-W