

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11-7-1963
NOV 7 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Glickman Oil Company,

Complete Address: 702 S. St. Francis, Wichita, Kansas.

Lease Name Horton Well No. 1

Location SW-SW-SE Sec. 2 Twp. 12 Rge. (E) (W) 21

County Tre go Total Depth 4068

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Barne s & Sons Pipe Pulling Company.

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 3:30PM Day 2 Month 11 Year 1963

The Above well was plugged as follows:

188' --10 3/4" Surface pipe, cement circulated.

4015' 7" cemented with 50 Sx.

Sanded well back to 4000' and set 5 Sx cement with dump bailer.

Pulled 7" to 600' and circulated heavy gel mud, (45 Sx. Gel) and displaced-

30 Sx. cement thru 7". Pulled 7" to 180' and displaced 30 Sx cement

thru 7". Pulled 7", set rock bridge @ 30' and 10 Sx cement to bottom of

cellar. Recovered 3691' 7" casing.

(Cementing and mudding operations performed by Halliburton Oil Well Cementing)

I hereby certify that the above well was plugged as herein stated.

DATE 11/8/63

INV. NO. 8038-u

Signed: W. L. D. Nichols
Well Plugging Supervisor