

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
8-14-1970  
AUG 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Glickman Oil Company,

Complete Address 702 So. St. Francis, Wichita, Kansas.

Lease Name Kohl Well No. 8

Location NW-NW-SW Sec. 2 Twp. 12 Rge. (E) (W) 21

County Trego Total Depth 4035'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Above

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 11:00 AM Day 3 Month 8 Year 1970

The above well was plugged as follows:

174'--8 5/8" Surface casing, cement circulated with 150 Sx.  
4024'--5 1/2" Production casing cemented on bottom with 50 Sx. DV tool @ 1770' with 450 Sx. cement to surface.

Squeezed 5 1/2" initially with 1 sack hulls and followed with 25 Sx. cement thru 23 sacks gel and finally 65 Sx. cement. Maximum pump-in pressure--2000#. Final shut-in pressure--1500#. (Mudding and cementing operations performed by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 8/14/70

INV. NO. 2380-U