

15-163-02228-00-02

~~15-163-19004-00-00~~  
~~15-163-90735-0000~~

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER \_\_\_\_\_  
LEASE NAME Trico East (LKC)  
WELL NUMBER #108W  
4290 Ft. from S Section Line  
2970 Ft. from E Section Line

RECEIVED  
STATE CORPORATION COMMISSION  
4-12-2000  
APR 12 2000

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

CONSERVATION DIVISION  
~~WICHITA CORPORATION~~

LEASE OPERATOR \_\_\_\_\_

SEC. 33 TWP. 10S RGE. 20 (E) or (W)

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

COUNTY Rooks

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed 3/3/55

Character of Well INJECTION

Plugging Commenced 3/29/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3/29/00

The plugging proposal was approved on 03/29/2000 (date)  
by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? YES

Producing Formation LKC Depth to Top 3529' Bottom 3612' T.D. 3714'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	250	-----
				5-1/2"	3690	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Perforated at 850 and 1625'. Ran tbg to 3100'. Spotted 50 sx 60/40 Pozmix w/10% gel, 300# hulls. Pull tbg to 2500' and spotted 10 sx gel. Pull tubing to 1750'. Spotted 135 sx same cement w/300# hulls. Cement circulated.

Pull tbg out of hole. Connected to 5-1/2" csg and pumped another 45 sx cement - 350#. Connected to 8-5/8 and 5-1/2" annulus and pumped 25 sx same cement w/100# hulls - 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P.O. Box 31- Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Pat Canaday (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

8100 E. 22nd St. N., Bldg. 300  
Wichita, KS 67226

SUBSCRIBED AND SWORN TO before me this 12th day of April, 2000

My Commission Expires:



Notary Public

Form CP-4  
Revised 05-88

# ALLIED CEMENTING CO., INC. 7845

Federal Tax I.D.#

15-163-02228-00-02

MIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Russel

DATE <u>3-29-00</u>	SEC.	TWP	RANGE	CALLED OUT <u>11:00 Am</u>	ON LOCATION <u>1:00 pm</u>	JOB START..	JOB FINISH <u>4:35 pm</u>
LEASE <u>Rico</u>	WELL # <u>E 108</u>	LOCATION <u>PALCO S E IN</u>			COUNTY <u>Rock</u>	STATE <u>Ka</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Smoky Hill

TYPE OF JOB Plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 8 3/8 DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT

AMOUNT ORDERED

275 lbs 60/40-10

200 # Hulls 10 lbs Gel Used 245 lbs

COMMON	<u>147</u>	@	<u>6.35</u>	<u>933.45</u>
POZMIX	<u>98</u>	@	<u>3.25</u>	<u>318.50</u>
GEL	<u>27</u>	@	<u>9.50</u>	<u>256.50</u>
CHLORIDE		@		
Hulls	<u>7</u>	@	<u>15.50</u>	<u>108.50</u>
		@		
		@		
		@		
		@		
HANDLING		@	<u>1.05</u>	<u>288.75</u>
MILEAGE	<u>44 SK</u>	/ mile		<u>363.00</u>
TOTAL				<u>2268.70</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

# 153 HELPER Paul

BULK TRUCK

# 254 DRIVER Ror

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Run Tubing 3000' spot 50 lbs Cem  
w/ 300 # Hull  
pull to 2800 spot 10 # Gel  
pull to 1700' Circ. Cem w/ 130 lbs  
w/ 300 # Hulls, pull Tubing  
pull down 5' w/ 40 lbs 30' # Shot IN  
pull down Ann w/ 25 lbs 300 # Shot IN

SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 450.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 33 @ 3.00 99.00

PLUG \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 549.00

CHARGE TO: Vess

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME \_\_\_\_\_

C. E. ALLPHIN NO. 8  
990'N 2310'W - Sec 33-10S-20W  
 Rooks County, Kansas

WELL RECORD

Operator: Continental Oil Company  
 Ponca City, Oklahoma

Contractor: Lehmann-Johnson Drilling Co., Inc.  
 320 Indiana Bank Building  
 Evansville, Indiana

Casing: Ran 9 Jts. 8-5/8" Surface Pipe set @ 250' w/175 Sacks  
 Ran 116 Jts. 5-1/2" set @ 3691' w/150 Sacks

Started: February 22, 1955  
 Completed: March 4, 1955

LOG

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>
0	251	Shale & Shells
251	605	Shale & Shells
605	730	Sand & Shale
730	1080	Shale & Shells
1080	1280	Sand
1280	1555	Shale & Shells
1555	1594	Shale
1594	1634	Anhydrite
1634	1815	Shale
1815	2095	Shale & Shells
2095	2275	Shale & Lime
2275	3075	Lime & Shale
3075	3185	Shale & Lime
3185	3285	Lime & Shale
3285	3342	Lime
3342	3542	Lime & Shale
3542	3695	Lime
3695		TOTAL DEPTH

SCC RFD SRC FLD (2)



3-29-1955