

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rooks

County. Sec. 33 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNWxSWx" or footage from lines 2200' FS & 440' FW lines Of

Lease Owner Continental Oil Company

Lease Name C. E. Allphin Well No. 2

Office Address Drawer 367, Plainville, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-17 19 60

Application for plugging filed (Verbal) 6-22 19 62

Application for plugging approved 6-22 19 62

Plugging commenced 6-22 19 62

Plugging completed 6-24 19 62

Reason for abandonment of well or producing formation

Field Experiment Completed.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation None Depth to top Bottom Total Depth of Well 1950 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	None
				5 1/2"	1875'	1875'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pulled 5 1/2" casing to 540' and pumped 14 sacks of mud and 20 sacks of cement at 540'. Pulled 5 1/2" casing to 220' and pumped 20 sacks of cement. Pulled balance of 5 1/2" casing, checked mud to 90', mudded to 35', set rock bridge to 30' and ran 10 sacks of cement to 4' below ground level.

RECEIVED
COMMISSION
7-20-1962
JUL 20 1962
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rooks ss.
L. E. Powell (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC
State Corp. Comm. (Signature) L. E. Powell

CRW
File Drawer 367, Plainville, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1962

My commission expires 12-2-65 Kenneth J. Query Notary Public.

